





MAGNETIC CHECK VALVE INSTALLATION INSTRUCTIONS

CFC, HCFC & HFC

Ambient



Operating Media



Medium temperature (500° F,
260°C) solder is preferred



Notes:

Ensure application does not exceed pressure stamped on valve.

Compatible with fluorinated refrigerants.

When installing vertically, ensure upward flow.