



MAGNETIC CHECK VALVE INSTALLATION INSTRUCTIONS

CFC, HCFC & HFC

Ambient



-60 → +175° F

-51 → +79° C

Operating Media



-40 → +300° F

-40 → +149° C



Medium temperature (500° F,
260°C) solder is preferred



Notes:

Ensure application does not exceed pressure stamped on valve.

Compatible with fluorinated refrigerants.

Failure to wet wrap may result in damage to the valve.